

BERAKAS POWER COMPANY SDN BHD

BERAKAS POWER STATION,
LEBUHRAYA RIMBA / JALAN UTAMA TERUNJING,
BERAKAS BB1514
NEGARA BRUNEI DARUSSALAM

Quotation Ref.	RFQ-2026-0689
----------------	----------------------

Project Title	Soil Investigation Works at Jalan Menteri Besar adjacent to Jalan Menteri Besar RC Road Bridge
---------------	---

Item	Description	Qty	Unit	Unit Rate	Amount (BND)
	<u>Notes</u> The quotation is called for the Soil Investigation of four (4) nos. of bore hole points adjacent to Jalan Menteri Besar RC Road Bridge as shown in Annexure #1 . The rates in these bills shall include supply, transportation, installation, dismantling, labour, cost to operate, duties & taxes, repatriation costs, temporary works or any other costs deemed necessary to complete the works as stated. All quantities stated herewith are provisional and subject to final re-measurement. The rates shall include all compliance with BPC's HSE requirements and the requirements as stipulated in the Ministry of Development's HSE Manual at all times, including adequate and qualified oversight of the safety of the site works, SHENA registered WSH Coordinator, provision of Personal Protective Equipment (PPE), submission of Risk Assessment and Method Statement (RAMS), and attending the BPC HSE Inductions for workers / Persons-In-Charge. Note: HSE Inductions are chargeable at B\$20 per worker. HSE Inductions for PICs are chargeable at B\$30 per person. The passes are valid for a year and renewals will cost B\$10 per person.				Included Included Included Included
1.0 1	<u>General and Preliminaries</u> General and preliminaries inclusive of site possession, mobilization, demobilization and re-mobilization of personnel and equipment to site, insurances to undertake the works at site, setting out of site and all associated works. Note: The Contractor has to submit a copy of their valid Workmen Compensation Insurance.	1	lot	B\$	B\$

BERAKAS POWER COMPANY SDN BHD

BERAKAS POWER STATION,
LEBUHRAYA RIMBA / JALAN UTAMA TERUNJING,
BERAKAS BB1514
NEGARA BRUNEI DARUSSALAM

Quotation Ref.	RFQ-2026-0689
----------------	----------------------

Project Title	Soil Investigation Works at Jalan Menteri Besar adjacent to Jalan Menteri Besar RC Road Bridge
---------------	---

Item	Description	Qty	Unit	Unit Rate	Amount (BND)
2.0	<u>Site Works</u> All works to refer to BS 5930: 2015, BS 1377: 1990 or equivalent.				
2.1	Setting out and providing coordinates and elevations of boreholes with reference to BRSO and Brunei State Datum, by a Licensed Surveyor.	1	lot	B\$	B\$
2.2	Drilling in soil at depth measured from natural ground, including all associated costs such as backfilling in boreholes for casing where necessary and measurement of ground water level:	1	lot	B\$	B\$
a.	Drill in soil (SPT N-value < 50) not exceeding 9m	36	m	B\$	B\$
b.	Ditto, exceeding 9m but not exceeding 18m	36	m	B\$	B\$
c.	Ditto, exceeding 18m but not exceeding 24m	24	m	B\$	B\$
d.	Ditto, exceeding 24m but not exceeding 30m	24	m	B\$	B\$
e.	Ditto, exceeding 30m	40	m	B\$	B\$
f.	Drill in hard strata (SPT N Value > 50)	24	m	B\$	B\$
2.3	Carry out Standard Penetration test at every 1.5m intervals	96	nos	B\$	B\$
2.4	Collection of disturbed samples	96	nos	B\$	B\$
2.5	Collection of undisturbed samples	16	nos	B\$	B\$
2.6	Field vane shear test in soft clayey strata	4	nos	B\$	B\$

BERAKAS POWER STATION,
LEBUHRAYA RIMBA / JALAN UTAMA TERUNJING,
BERAKAS BB1514
NEGARA BRUNEI DARUSSALAM

Project Title	Soil Investigation Works at Jalan Menteri Besar adjacent to Jalan Menteri Besar RC Road Bridge
---------------	---

Page 3 of 5

BERAKAS POWER COMPANY SDN BHD

BERAKAS POWER STATION,
LEBUHRAYA RIMBA / JALAN UTAMA TERUNJING,
BERAKAS BB1514
NEGARA BRUNEI DARUSSALAM

Quotation Ref.	RFQ-2026-0689
----------------	----------------------

Project Title	Soil Investigation Works at Jalan Menteri Besar adjacent to Jalan Menteri Besar RC Road Bridge
---------------	---

Item	Description	Qty	Unit	Unit Rate	Amount (BND)
4.0	<u>Reporting and Submission</u>				
4.1	To provide preliminary logs of boreholes and field data of in-situ tests in soft copy.	1	Lot	B\$	B\$
4.2	Prepare and submit one (1) draft and one (1) finalized original of a signed factual report by Engineering Geologist or Geotechnical Engineer on site conditions incorporating the results of all field & laboratory testing, in hard copy and soft copy (DVD or USB drive).	1	Lot	B\$	B\$
GRAND TOTAL AMOUNT					B\$

Required Commencement Date: Estimated W2 August 2026

Guaranteed Completion Period: _____ Days from instruction to Proceed

Quotation validity: 1 months from the Submission Date

Company Name

Stamp & Signature

Date

BERAKAS POWER COMPANY SDN BHD

BERAKAS POWER STATION,
LEBUHRAYA RIMBA / JALAN UTAMA TERUNJING,
BERAKAS BB1514
NEGARA BRUNEI DARUSSALAM

Quotation Ref.	RFQ-2026-0689
Project Title	Soil Investigation Works at Jalan Menteri Besar adjacent to Jalan Menteri Besar RC Road Bridge

ANNEXURE # 1 – SITE OVERVIEW

